

Proceedings No. HDO (B) / 65325 / 2001, dated 25.07.2013

Sub: Buildings - Common Schedule of Plinth Area Rates for the purpose of valuation of buildings for rental purpose by Public Works Department and Collection of Stamp Duty by Registration Department - **Approved for the year 2013-2014 and communicated for adoption with effect from 01.07.2013** - Regarding.

Ref: Engineer-in-Chief (Buildings) & Chief Engineer (Buildings) & Chief Engineer (General), PWD, Chennai-5, Proceedings No. HDO (B) / 65325 / 2001, dated 31.07.2012.

The common Schedule of Plinth Area Rates for arriving at the valuation of buildings for rental purpose by PWD and for collection of Stamp Duty by Registration Department during the year 2013-2014 is hereby approved and communicated in Annexure-I for adoption with effect from **01.07.2013**. The approved rates shall be in operation for One Year (i.e.) upto 30.06.2014. 1.8.2013

The Chief Engineers, the Superintending Engineers and the Executive Engineers of Building Organisation are requested to adopt the above rates in working out the rental calculation of buildings referred-to, to them.

The receipt of this proceeding together with Annexure-I shall be acknowledged.

Encl.: Annexure-I

To

The Chief Engineer (Buildings), PWD, Trichy Region, Trichy.
The Chief Engineer (Buildings), PWD, Madurai Region, Madurai.

Copy with enclosures to:

The Superintending Engineers of Building Organisation, Public Works Department.
The Executive Engineers of Building Organisation, Public Works Department.
The Senior Audit Officer, Indian Audit and Accounts Department, Accountant General (Audit) II, Chennai-18.
The Inspector General of Registration, No.100, Santhome High Road, Chennai-28.
Copy to the Joint Chief Engineer (Buildings), PWD, Chennai-5.
Copy to the Deputy Chief Engineer (Buildings), PWD, Chennai-5.
Copy to HDO, AEEs of all Technical Sections of EIC (B) & CE (B), CR & CE (GL) Office.
Copy to Stock File / Copy to File / Spare copies (50 Nos.)

25/7/13
1.8.2013

(11)

OFFICE OF THE ENGINEER-IN-CHIEF (BUILDINGS) &
CHIEF ENGINEER (BUILDINGS), CHENNAI REGION &
CHIEF ENGINEER (GENERAL), PWD., CHEPAUK, CHENNAI-5

ANNEXURE-I

PROPOSAL FOR THE APPROVAL OF COMMON SCHEDULE OF PLINTH AREA RATES
FOR THE PREPARATION OF RENTAL VALUATION OF BUILDINGS
DURING THE YEAR 2013-2014
[WITH EFFECT FROM 01.07.2013]

	Plinth area rate for valuation of buildings with reference to the plinth area for each type of construction (excluding cost of land)
	General Note to be followed in arriving at the Rental Valuation of Buildings
a.	The rates approved and furnished below vide Sl. No. I to XV are applicable commonly to the entire State, subject to the following provisions:
i.	An extra 20% shall be added to the rates approved vide Sl. No. I to XII below for valuation of Buildings within Chennai Corporation limits and its belt area of 32 km around Chennai Corporation limit.
ii.	An extra 15% shall be added to the rates approved vide Sl. No. I to XII below for valuation of Buildings within Coimbatore, Erode and Tiruppur Corporation limits
iii.	An extra 10% shall be added to the rates approved vide Sl. No. I to XII below for valuation of Buildings within Corporation limits of Trichy, Madurai, Salem, Tirunelveli, Thoothukudi and Vellore
iv.	An extra 5% shall be added to the rates approved vide Sl. No. I to XII below for valuation of Buildings within all Municipal limits.
v.	An extra 10% shall be added to the rates approved vide Sl. No. I to XII below for valuation of Buildings located in Nilgiris, Kodaikanal and Yercaud hills, where tourist attractions are more.
b.	The filed Officers are requested to follow the instructions contained in G.O. Ms. No. 329, Finance (Salaries) Department, dated 30.08.2001 in fixation of either new rent or renewal of rent scrupulously, so that there shall not be any extra financial burden to the Government towards the payment of rent to the Private Buildings occupied by the Government Offices.

Sl. No.	Type of construction	Unit	Rates approved for the year 2013-2014 (In Rupees)
I	Class-A		
	Building built with Brick work in lime mortar (or) cement mortar in which teak wood has been used throughout		
1	Roof with RCC Slab		
a	Ground Floor		
b	First Floor	Sq.m.	5845.00
c	Second Floor	Sq.m.	5420.00
d	Other upper floors (add extra for each floors)	Sq.m.	5510.00
2	Roof with Madras Terrace	Sq.m.	83.10
a	Ground Floor		
b	First Floor	Sq.m.	5345.00
c	Second Floor	Sq.m.	5010.00
d	Other upper floors (add extra for each floors)	Sq.m.	5090.00
3	Roof with Mangalore Tiles over Flat Tiles	Sq.m.	83.10
a	Ground Floor		
b	First Floor	Sq.m.	4255.00
c	Second Floor	Sq.m.	3925.00
d	Other upper floors (add extra for each floors)	Sq.m.	4000.00
4	Roof with Plain Mangalore Tiles	Sq.m.	66.00
a	Ground Floor		
b	First Floor	Sq.m.	4000.00
c	Second Floor	Sq.m.	3670.00
d	Other upper floors (add extra for each floors)	Sq.m.	3755.00
5	Roof with Pan Tiles over Flat Tiles	Sq.m.	66.00
a	Ground Floor		
b	First Floor	Sq.m.	3925.00
c	Second Floor	Sq.m.	3590.00
d	Other upper floors (add extra for each floors)	Sq.m.	3670.00
6	Roof with Pan Tiles without Flat Tiles	Sq.m.	66.00
a	Ground Floor		
		Sq.m.	3500.00

Sl. No.	Type of construction	Unit	Rates approved for the year 2013-2014 (In Rupees)
b	First Floor	Sq.m.	3170.00
c	Second Floor	Sq.m.	3255.00
d	Other upper floors (add extra for each floors)	Sq.m.	66.00
7	Roof with AC Sheet		
a	Ground Floor	Sq.m.	3335.00
b	First Floor	Sq.m.	3000.00
c	Second Floor	Sq.m.	3090.00
d	Other upper floors (add extra for each floors)	Sq.m.	66.00
8	Roof with GI Sheet		
a	Ground Floor	Sq.m.	3425.00
b	First Floor	Sq.m.	3090.00
c	Second Floor	Sq.m.	3170.00
d	Other upper floors (add extra for each floors)	Sq.m.	66.00
	RATE OF DEPRECIATION		1%

Sl. No.	Type of construction	Unit	Rates approved for the year 2013-2014 (In Rupees)
II	Class-A1		
	Building built with Brick work in lime mortar (or) cement mortar in which country wood has been used throughout		
1	Roof with RCC Slab		
a	Ground Floor	Sq.m.	5255.00
b	First Floor	Sq.m.	4755.00
c	Second Floor	Sq.m.	4850.00
d	Other upper floors (add extra for each floors)	Sq.m.	83.10
2	Roof with Madras Terrace		
a	Ground Floor	Sq.m.	4755.00
b	First Floor	Sq.m.	4345.00
c	Second Floor	Sq.m.	4420.00
d	Other upper floors (add extra for each floors)	Sq.m.	83.10
3	Roof with Mangalore Tiles over Flat Tiles		
a	Ground Floor	Sq.m.	3755.00
b	First Floor	Sq.m.	3255.00
c	Second Floor	Sq.m.	3335.00
d	Other upper floors (add extra for each floors)	Sq.m.	66.00
4	Roof with Plain Mangalore Tiles		
a	Ground Floor	Sq.m.	3425.00
b	First Floor	Sq.m.	3000.00
c	Second Floor	Sq.m.	3090.00
d	Other upper floors (add extra for each floors)	Sq.m.	66.00
5	Roof with Pan Tiles over Flat Tiles		
a	Ground Floor	Sq.m.	3335.00
b	First Floor	Sq.m.	3000.00
c	Second Floor	Sq.m.	3090.00
d	Other upper floors (add extra for each floors)	Sq.m.	66.00

Sl. No.	Type of construction	Unit	Rates approved for the year 2013-2014 (In Rupees)
6	Roof with Pan Tiles without Flat Tiles		
a	Ground Floor	Sq.m.	3000.00
b	First Floor	Sq.m.	2670.00
c	Second Floor	Sq.m.	2750.00
d	Other upper floors (add extra for each floors)	Sq.m.	66.00
7	Roof with AC Sheet		
a	Ground Floor	Sq.m.	3090.00
b	First Floor	Sq.m.	2750.00
c	Other upper floors (add extra for each floors)	Sq.m.	66.00
8	Roof with GI Sheet		
a	Ground Floor	Sq.m.	3220.00
b	First Floor	Sq.m.	2880.00
c	Other upper floors (add extra for each floors)	Sq.m.	66.00
	RATE OF DEPRECIATION		1%

Sl. No.	Type of construction	Unit	Rates approved for the year 2013-2014 (In Rupees)
III	Class-B		
	Building built with Brick work in lime mortar (or) cement mortar & partly mud mortar in which teak wood has been used throughout		
1	Roof with RCC Slab		
a	Ground Floor		
b	First Floor	Sq.m.	4755.00
c	Second Floor	Sq.m.	4345.00
d	Other upper floors (add extra for each floors)	Sq.m.	4420.00
2	Roof with Madras Terrace	Sq.m.	83.10
a	Ground Floor		
b	First Floor	Sq.m.	4255.00
c	Second Floor	Sq.m.	3925.00
d	Other upper floors (add extra for each floors)	Sq.m.	4000.00
3	Roof with Mangalore Tiles over Flat Tiles	Sq.m.	83.10
a	Ground Floor		
b	First Floor	Sq.m.	3335.00
c	Second Floor	Sq.m.	2920.00
d	Other upper floors (add extra for each floors)	Sq.m.	3000.00
4	Roof with Plain Mangalore Tiles	Sq.m.	66.00
a	Ground Floor		
b	First Floor	Sq.m.	3090.00
c	Second Floor	Sq.m.	2670.00
d	Other upper floors (add extra for each floors)	Sq.m.	2750.00
5	Roof with Pan Tiles over Flat Tiles	Sq.m.	66.00
a	Ground Floor		
b	First Floor	Sq.m.	2925.00
c	Second Floor	Sq.m.	2585.00
d	Other upper floors (add extra for each floors)	Sq.m.	2670.00
		Sq.m.	66.00

Sl. No.	Type of construction	Unit	Rates approved for the year 2013-2014 (In Rupees)
6	Roof with Pan Tiles without Flat Tiles		
a	Ground Floor	Sq.m.	2670.00
b	First Floor	Sq.m.	2335.00
c	Second Floor	Sq.m.	2420.00
d	Other upper floors (add extra for each floors)	Sq.m.	66.00
7	Roof with AC Sheet		
a	Ground Floor	Sq.m.	2750.00
b	First Floor	Sq.m.	2420.00
c	Other upper floors (add extra for each floors)	Sq.m.	66.00
8	Roof with GI Sheet		
a	Ground Floor	Sq.m.	2835.00
b	First Floor	Sq.m.	2500.00
c	Other upper floors (add extra for each floors)	Sq.m.	66.00
	RATE OF DEPRECIATION		1.50%

Sl. No.	Type of construction	Unit	Rates approved for the year 2013-2014 (In Rupees)
IV	Class-B1		
	Building built with Brick work in lime mortar (or) cement mortar and partly in mud mortar in which country wood has been used throughout		
1	Roof with RCC Slab		
a	Ground Floor	Sq.m.	4345.00
b	First Floor	Sq.m.	3925.00
c	Second Floor	Sq.m.	4000.00
d	Other upper floors (add extra for each floors)	Sq.m.	83.10
2	Roof with Madras Terrace		
a	Ground Floor	Sq.m.	3835.00
b	First Floor	Sq.m.	3500.00
c	Second Floor	Sq.m.	3590.00
d	Other upper floors (add extra for each floors)	Sq.m.	83.10
3	Roof with Mangalore Tiles over Flat Tiles		
a	Ground Floor	Sq.m.	3000.00
b	First Floor	Sq.m.	2670.00
c	Second Floor	Sq.m.	2750.00
d	Other upper floors (add extra for each floors)	Sq.m.	66.00
4	Roof with Plain Mangalore Tiles		
a	Ground Floor	Sq.m.	2750.00
b	First Floor	Sq.m.	2420.00
c	Second Floor	Sq.m.	2505.00
d	Other upper floors (add extra for each floors)	Sq.m.	66.00
5	Roof with Pan Tiles over Flat Tiles		
a	Ground Floor	Sq.m.	2585.00
b	First Floor	Sq.m.	2255.00
c	Second Floor	Sq.m.	2335.00
d	Other upper floors (add extra for each floors)	Sq.m.	66.00

Sl. No.	Type of construction	Unit	Rates approved for the year 2013-2014 (In Rupees)
6	Roof with Pan Tiles without Flat Tiles		
a	Ground Floor	Sq.m.	2505.00
b	First Floor	Sq.m.	2170.00
c	Second Floor	Sq.m.	2255.00
d	Other upper floors (add extra for each floors)	Sq.m.	66.00
7	Roof with AC Sheet		
a	Ground Floor	Sq.m.	2585.00
b	First Floor	Sq.m.	2255.00
c	Other upper floors (add extra for each floors)	Sq.m.	66.00
8	Roof with GI Sheet		
a	Ground Floor	Sq.m.	2670.00
b	First Floor	Sq.m.	2335.00
c	Other upper floors (add extra for each floors)	Sq.m.	66.00
	RATE OF DEPRECIATION		2%

Sl. No.	Type of construction	Unit	Rates approved for the year 2013-2014 (In Rupees)
V	Class-C		
	Building built with brick work in mud mortar in which country wood has been used throughout		
1	Roof with RCC Slab		
a	Ground Floor	Sq.m.	3685.00
b	First Floor	Sq.m.	3255.00
2	Roof with Madras Terrace		
a	Ground Floor	Sq.m.	3335.00
b	First Floor	Sq.m.	3000.00
3	Roof with Mangalore Tiles over Flat Tiles		
a	Ground Floor	Sq.m.	2585.00
b	First Floor	Sq.m.	2335.00
4	Roof with Plain Mangalore Tiles		
a	Ground Floor	Sq.m.	2335.00
b	First Floor	Sq.m.	2080.00
5	Roof with Pan Tiles over Flat Tiles		
a	Ground Floor	Sq.m.	2255.00
b	First Floor	Sq.m.	2005.00
6	Roof with Pan Tiles without Flat Tiles		
a	Ground Floor	Sq.m.	2080.00
b	First Floor	Sq.m.	1915.00
7	Roof with AC Sheet		
a	Ground Floor	Sq.m.	2335.00
b	First Floor	Sq.m.	2080.00
8	Roof with GI Sheet		
a	Ground Floor	Sq.m.	2420.00
b	First Floor	Sq.m.	2170.00
	RATE OF DEPRECIATION		2%

Sl. No.	Type of construction	Unit	Rates approve for the year 2013-2014 (In Rupees)
VI	Class-D		
	Building built with brick work in lime or cement mortar in which partly wood and partly steel has been used throughout		
1	Roof with RCC Slab		
a	Ground Floor		
b	First Floor	Sq.m.	3755.00
c	Second Floor	Sq.m.	3335.00
d	Other upper floors (add extra for each floors)	Sq.m.	3425.00
2	Roof with Madras Terrace	Sq.m.	83.10
a	Ground Floor		
b	First Floor	Sq.m.	3425.00
c	Second Floor	Sq.m.	3090.00
d	Other upper floors (add extra for each floors)	Sq.m.	3170.00
3	Roof with Mangalore Tiles over Flat Tiles	Sq.m.	83.10
a	Ground Floor		
b	First Floor	Sq.m.	2670.00
c	Second Floor	Sq.m.	2420.00
d	Other upper floors (add extra for each floors)	Sq.m.	2505.00
4	Roof with Plain Mangalore Tiles	Sq.m.	66.00
a	Ground Floor		
b	First Floor	Sq.m.	2420.00
c	Second Floor	Sq.m.	2170.00
d	Other upper floors (add extra for each floors)	Sq.m.	2255.00
5	Roof with Pan Tiles over Flat Tiles	Sq.m.	66.00
a	Ground Floor		
b	First Floor	Sq.m.	2335.00
c	Second Floor	Sq.m.	2080.00
d	Other upper floors (add extra for each floors)	Sq.m.	2170.00
		Sq.m.	66.00

Sl. No.	Type of construction	Unit	Rates approved for the year 2013-2014 (In Rupees)
6	Roof with Pan Tiles without Flat Tiles		
a	Ground Floor	Sq.m.	2170.00
b	First Floor	Sq.m.	2005.00
c	Second Floor	Sq.m.	2070.00
d	Other upper floors (add extra for each floors)	Sq.m.	66.00
7	Roof with AC Sheet		
a	Ground Floor	Sq.m.	2420.00
b	First Floor	Sq.m.	2080.00
c	Other upper floors (add extra for each floors)	Sq.m.	66.00
8	Roof with GI Sheet		
a	Ground Floor	Sq.m.	2505.00
b	First Floor	Sq.m.	2255.00
c	Other upper floors (add extra for each floors)	Sq.m.	66.00
	RATE OF DEPRECIATION		1.50%

14

Sl. No.	Type of construction	Unit	Rates approved for the year 2013-2014 (In Rupees)
VII	Class-D1		
	Building built with brick in lime or cement mortar in which steel frame is used throughout		
1	Roof with RCC Slab		
a	Ground Floor		
b	First Floor	Sq.m.	3930.00
c	Second Floor	Sq.m.	3495.00
d	Other upper floors (add extra for each floors)	Sq.m.	3590.00
2	Roof with Madras Terrace	Sq.m.	84.40
a	Ground Floor		
b	First Floor	Sq.m.	3590.00
c	Second Floor	Sq.m.	3245.00
d	Other upper floors (add extra for each floors)	Sq.m.	3330.00
3	Roof with Mangalore Tiles over Flat Tiles	Sq.m.	84.40
a	Ground Floor		
b	First Floor	Sq.m.	2815.00
c	Second Floor	Sq.m.	2565.00
d	Other upper floors (add extra for each floors)	Sq.m.	2645.00
4	Roof with Plain Mangalore Tiles	Sq.m.	68.60
a	Ground Floor		
b	First Floor	Sq.m.	2565.00
c	Second Floor	Sq.m.	2310.00
d	Other upper floors (add extra for each floors)	Sq.m.	2385.00
5	Roof with Pan Tiles over Flat Tiles	Sq.m.	68.60
a	Ground Floor		
b	First Floor	Sq.m.	2475.00
c	Second Floor	Sq.m.	2220.00
d	Other upper floors (add extra for each floors)	Sq.m.	2310.00
		Sq.m.	68.60

14

Sl. No.	Type of construction	Unit	Rates approved for the year 2013-2014 (In Rupees)
6	Roof with Pan Tiles without Flat Tiles		
a	Ground Floor		
b	First Floor	Sq.m.	2310.00
c	Second Floor	Sq.m.	2130.00
d	Other upper floors (add extra for each floors)	Sq.m.	2205.00
7	Roof with AC Sheet		
a	Ground Floor		
b	First Floor	Sq.m.	2565.00
c	Other upper floors (add extra for each floors)	Sq.m.	2220.00
8	Roof with GI Sheet		
a	Ground Floor		
b	First Floor	Sq.m.	2645.00
c	Other upper floors (add extra for each floors)	Sq.m.	2385.00
	RATE OF DEPRECIATION	Sq.m.	68.60
			1%

Sl. No.	Type of construction	Unit	Rates approved for the year 2013-2014 (In Rupees)
VIII	Class-E - RCC FRAMED STRUCTURE		
1	Framed structure building built in CM in which TW is used for construction (excluding water supply, sanitary and electrical installations)		
a	Ground Floor	Sq.m.	6490.00
b	First Floor	Sq.m.	6065.00
c	Second Floor	Sq.m.	6145.00
d	Third Floor	Sq.m.	6230.00
e	Other upper floors (add extra for each floors)	Sq.m.	84.40
2	Balcony / Portico projecting outside the face of the building with hand rail with brick work/wood/grill	Sq.m.	2220.00
	RATE OF DEPRECIATION		1%
IX	GODOWN		
2 a	For godowns / Hall type construction with RCC columns and connecting beams etc. with steel trusses and purlins		
	Roofing with A/C sheet	Sq.m.	4860.00
	Roofing with G.I. sheet	Sq.m.	5040.00
b	For godowns / Hall type construction with load bearing type construction with steel trusses and purlins		
	Roofing with A/C sheet	Sq.m.	4510.00
	Roofing with G.I. sheet	Sq.m.	4590.00
	RATE OF DEPRECIATION		1%

SL No.	Type of construction	Unit	Rates approved for the year 2013-2014 (In Rupees)
X	Building built with brick work in mud mortar and partly with RR masonry in mud mortar and brick jelly concrete in lime for foundation and ordinary flooring; roofing with RCC/Madras Terrace in which country wood has been used throughout		
1	Roof with RCC slab		
	Ground Floor	Sq.m.	4090.00
	First Floor	Sq.m.	3500.00
2	Roof with Madras Terrace		
a	Ground Floor	Sq.m.	3590.00
b	First Floor	Sq.m.	3090.00
3	Roof with Mangalore Tiles over Flat Tiles		
a	Ground Floor	Sq.m.	2750.00
b	First Floor	Sq.m.	2335.00
4	Roof with Plain Mangalore Tiles		
a	Ground Floor	Sq.m.	2505.00
b	First Floor	Sq.m.	2170.00
5	Roof with Pan Tiles over Flat Tiles		
a	Ground Floor	Sq.m.	2335.00
b	First Floor	Sq.m.	2005.00
6	Roof with Pan Tiles without Flat Tiles		
a	Ground Floor	Sq.m.	2255.00
b	First Floor	Sq.m.	1915.00
7	Roof with AC Sheet		
a	Ground Floor	Sq.m.	2420.00
b	First Floor	Sq.m.	2005.00
8	Roof with GI Sheet		
a	Ground Floor	Sq.m.	2505.00
b	First Floor	Sq.m.	2080.00
	RATE OF DEPRECIATION		2.50%


Sl. No.	Type of construction	Unit	Rates approved for the year 2013-2014 (In Rupees)
XI	THATCHED / TILED ROOF		
1	Building built with brick work in clay and plastered with lime mortar or cement mortar, ordinary grano flooring, white or colour washed, thatched roof either with coconut leaves or palmyrah leaves over CW or bamboo rafters, etc.		
a	Ground Floor	Sq.m.	1900.00
2	Building built with plain mud walls plastered with mud mortar and thatched roof either with coconut leaves of palmyrah leaves over bamboo or country wood rafters etc.		
a	Ground Floor	Sq.m.	950.00
3	Building built with plain mud walls and plastered with mud mortar & roof with mangalore tiles using bamboo or country wood rafters etc.	Sq.m.	1255.00
4	Building built with plain mud walls and plastered with mud mortar and roof with pan tiles using bamboo or country wood rafters	Sq.m.	1110.00
5	Building built with plain mud walls and plastered with mud mortar and roof with A/C sheet	Sq.m.	1345.00
6	Building built with plain mud walls and plastered with mud mortar and roof with G.I. sheet	Sq.m.	1380.00
	RATE OF DEPRECIATION		4%
XII	GARAGE BUILDINGS		
a	Garage buildings built with brick work in lime or cement mortar and roof with RCC slab in which teak wood or rolling shutters used.	Sq.m.	2505.00
b	Garage building built with brick work in lime or cement mortar with mangalore tile or pan tile roof over flat tiles in which teak wood or rolling shutters used.	Sq.m.	2335.00
	RATE OF DEPRECIATION		1%
c	Garage buildings built with brick work in partly clay and partly lime or cement mortar and roof with RCC slab in which country wood used throughout.	Sq.m.	2420.00
d	Garage building built with brick work in partly clay and partly lime or cement mortar with mangalore tiles or pan tiles roof over flat tiles in which country wood used throughout.	Sq.m.	2080.00
	RATE OF DEPRECIATION		2%

Sl. No.	Type of construction	Unit	Rates approved for the year 2013-2014 (In Rupees)
XIII	MISCELLANEOUS ITEMS		
1	Open area paved either with cement concrete (or) brick (or) stone slabs with retaining walls	Sq.m.	473.00
2	Fencing the area with RCC post and covered either with barbed wire or chain link 1.65m height from Ground level.	RM	357.00
	RATE OF DEPRECIATION		4%
3	Compound wall built in cement or lime mortar to a height of 1.20 metre to 1.50 metre		
	i. Ordinary type 4 1/2" wall thick	RM	836.00
	ii. Ornamental type 9" wall thick	RM	1254.00
4	i. Mosaic flooring grey colour tiles	Sq.m.	473.00
	ii. Mosaic flooring with colour tiles (other than grey)	Sq.m.	533.00
	iii. Dadoing with mosaic in situ	Sq.m.	462.00
5	Cuddapah slab/Shahabad slab flooring	Sq.m.	335.00
6	Flooring with granite slabs 18 to 20mm thick	Sq.m.	1835.00
7	i. Flooring with vitrified tiles	Sq.m.	1210.00
	ii. Dadoing with vitrified tiles	Sq.m.	1045.00
8	i. Flooring with ceramic tiles	Sq.m.	533.00
	ii. Dadoing with Ceramic / glazed tiles	Sq.m.	462.00
9	i. Flooring with marble tiles	Sq.m.	918.00
	ii. Flooring with marble slabs		
	a. for slab of size 1.20 metre and above	Sq.m.	1330.00
	b. for slab of size below 1.20 metre	Sq.m.	1083.00
	RATE OF DEPRECIATION		2%

Sl. No.	Type of construction	Unit	Rates approved for the year 2013-2014 (In Rupees)
10	Iron gates (1.2m height & 3m width)		
	i. Iron gates with ornamental grill	Sq.m.	1300.00
	ii. Iron gates with GI pipe around & weld mesh inbetween	Sq.m.	810.00
11	Rolling shutters	Sq.m.	1705.00
12	Over head tanks		
	i. In brick work / litre	litre	2.30
	ii. PVC tanks / litre	litre	3.45
13	Municipal Water Tap Service connection	Each	2190.00
14	Hand pump	Each	2190.00
15	Bore well		
	i. upto 50 metre depth / m	RM	120.00
	ii. 50 to 100 metre depth	RM	126.00
	iii. 100 to 200 metre depth	RM	131.00
16	i. Open Well 1.20 metre dia with brick steining 7.50 metre deep	Each	680.00
	ii. Open well 1.50 metre dia with brick steining 7.50 metre deep	Each	14610.00
	iii. Open well 1.80 metre dia with brick steining 7.50 metre deep	Each	17525.00
	iv. Open well 2.00 metre dia with brick steining 7.50 metre deep	Each	21180.00
17	i. False ceiling using aluminium tees, angles with particle board 60 x 60cm size	Sq.m.	610.00
	ii. Using plywood 5mm thick	Sq.m.	429.00
18	Septic tank built in brick work in cement mortar precast cover slab with inlet and outlet (On volume basis)		
	for 1 cum capacity	Cu.m.	6880.00
19	Inspection chambers with RCC cover slab built in brick work in cement mortar, 23cm thick, plastered and finished		
	i. 60 x 60 x 60cm size	Each	1375.00
	ii. 60 x 60 x 75cm size	Each	1675.00
	iii. 60 x 60 x 90cm size	Each	2065.00

Sl. No.	Type of construction	Unit	Rates approved for the year 2013-2014 (In Rupees)
20	i. Providing IWC with water line, tap, flush out system etc.	Each	3365.00
	ii. Providing EWC 580mm with water line, tap, flush out system etc.	Each	4275.00
21	Wash basin including water line, tap, etc.	Each	1525.00
22	Provision of towel rod and mirror or size 550x440mm	Each	687.00
23	Flat back urinal with water line, valves, etc	Each	918.00
24	Sink with water line, tap, etc	Each	1525.00
25	Open latrine with 1.80 metre height wall built in brick work in cement mortar.	Sq.m.	2135.00
26	i. Bathroom with GI water line, taps, shower line etc. (minimum room size 1.50m x 1.35m)	Each	3055.00
	ii. Bathroom with PVC water line, tap, shower line, etc. (minimum room size 1.50m x 1.35m)	Each	2675.00
	iii. Bath Tub with all accessories (Porcelain)	Each	11470.00
	iv. Bath Tub with all accessories (built with mosaic finish)	Each	3055.00
XIV I. External Services			
1	50mm dia CI pipe line and specials	RM	379.00
2	75mm dia CI pipe line and specials	RM	533.00
3	100mm dia SW pipe line and specials	RM	120.00
4	150mm dia SW pipe line and specials	RM	198.00
5	100mm dia PVC pipe line and specials	RM	225.00
6	75mm dia PVC pipe line and specials	RM	137.00
II. For Internal			
1	Water supply arrangements (maximum)	on value of building	7.50%
2	Internal sanitary arrangements (maximum)	on value of building	7.50%
3	Internal electrical arrangements (maximum)	on value of building	7.50%

Sl. No.	Type of construction	Unit	Rates approved for the year 2013-2014 (In Rupees)
XV	ELECTRICAL ITEMS		
1	Plug point	Each	194.00
2	Fan point	Each	231.00
3	Light point	Each	220.00
4	1.20m flourescent fitting patty type with tube		
	i. Single	Each	325.00
	ii. Double	Each	590.00
5	40 W flourescent tube (single)	Each	65.00
6	1.20m flourescent fitting box type with tube		
	i. Single	Each	462.00
	ii. Double	Each	724.00
7	i. 1.20m sweep AC ceiling fan with regulator	Each	1585.00
	ii. 1.40m sweep AC ceiling fan with regulator	Each	1710.00
8	EXHAUST FAN	Each	1395.00
9	0.50 HP electric motor pump set		
	i. centrifugal	Each set	6280.00
	ii. Jet type	Each set	8030.00
10	1.00 HP electric motor pump set		
	i. Centrifugal	Each set	7680.00
	ii. Jet	Each set	9430.00
11	1.50 HP electric motor pump set		
	i. Centrifugal	Each set	9080.00
	ii. Jet	Each set	11870.00
12	2.00 HP electric motor pump set		
	i. Centrifugal	Each set	11170.00
	ii. Jet	Each set	14320.00
13	3.00 HP electric motor pump set		
	i. Centrifugal	Each set	13970.00
	ii. Jet	Each set	18860.00
14	5.00 H.P. electric motor pump set (JET)	Each set	23050.00
15	Air-conditioning (on floor area basis)		
	a. Non-Ductable	Sq.m.	3150.00
	b. Ductable	Sq.m.	4200.00
16	i. Lift (G.F. + 4 floors - 8 Passenger capacity)	Each	1200000.00
	ii. Lift (G.F. + 4 floors - 15 Passenger capacity)	Each	1500000.00


 for Engineer-in-Chief (Buildings) &
 Chief Engineer (Buildings), Chennai Region &
 Chief Engineer (General), PWD.

25/07/13
 25/07/13

Ren
 dur
 add
 Ye:

Bu
 cal

Er

T

T

T

C

T

(

(

(

(