

**OFFICE OF THE ENGINEER-IN-CHIEF (BUILDINGS) &
CHIEF ENGINEER (BUILDINGS), PWD, CHENNAI REGION,
CHEPAUK, CHENNAI-5**

Present: **Er. S. Sampath, M.E.,**
Engineer-in-Chief (Buildings) &
Chief Engineer (Buildings), PWD,
Chennai Region, Chennai-5.

Proceedings No. HDO (B) / 65325 / 2001, dated 24.08.2015

Sub: Buildings – Common Schedule of Plinth Area Rates for the Valuation of Buildings for Rental Calculation Purpose by Public Works Department and for the purpose of Collection of Stamp Duty by Registration Department – **Approved for the year 2015-2016 for adoption with effect from 01.08.2015** – Communication of – Regarding.

Ref: Engineer-in-Chief (Buildings) & Chief Engineer (Buildings) & Chief Engineer (General), PWD, Chennai-5, Proceedings No. HDO (B) / 65325 / 2001, dated 31.07.2014.




The common Schedule of Plinth Area Rates for the Valuation of Buildings (i) for Rental Calculation Purpose by PWD and (ii) for Collection of Stamp Duty by Registration Department during the year **2015-2016** is hereby approved and enclosed vide Annexure-I for adoption with effect from **01.08.2015**. The approved rates shall be in operation for **One Year (i.e.) upto 31.07.2016**.

The Chief Engineers, the Superintending Engineers and the Executive Engineers of Building Organisation are requested to adopt the above rates in working out the rental calculation of buildings.

The receipt of this proceeding together with Annexure-I shall be acknowledged.

Encl.: Annexure-I


for Engineer-in-Chief (Buildings) &
Chief Engineer (Buildings), PWD,
Chennai Region, Chennai-5
24/08/15

To

The Chief Engineer (Buildings), PWD, Trichy Region, Trichy.
The Chief Engineer (Buildings), PWD, Madurai Region, Madurai.

Copy with Annexure-I communicated to:

The Superintending Engineers of Building Organisation, Public Works Department.
The Executive Engineers of Building Organisation, Public Works Department.
The Senior Audit Officer, Indian Audit and Accounts Department, Accountant General (Audit) II, Chennai-18.
The Inspector General of Registration, No.100, Santhome High Road, Chennai-28.
Copy to the Joint Chief Engineer (Buildings), PWD, Chennai-5.
Copy to the Deputy Chief Engineer (Buildings), PWD, Chennai-5.
Copy to HDO, AEEs of all Technical Sections of EIC (B) & CE (B), CR, PWD, Chennai-5.
Copy to Stock File / Copy to File / Spare copies (50 Nos.).

ANNEXURE-I

**COMMON SCHEDULE OF PLINTH AREA RATES FOR THE VALUATION OF BUILDINGS
FOR RENTAL CALCULATION PURPOSE BY PWD AND FOR THE PURPOSE OF
COLLECTION OF STAMP DUTY BY REGISTRATION DEPARTMENT
DURING THE YEAR 2015-2016
[WITH EFFECT FROM 01.08.2015]**

	The common Schedule of Plinth Arera Rates for the valuation of buildings with reference to the plinth area for each type of construction (excluding cost of land) shall be arrived at as given below.
	General Note to be followed in arriving at the Rental Valuation of Buildings
a.	The rates approved and furnished below vide Sl. No. I to XV are applicable commonly to the entire State, subject to the following provisions:
i.	An extra 20% shall be added to the rates approved vide Sl. No. I to XII below for valuation of Buildings within Chennai Corporation limits and its belt area of 32 km around Chennai Corporation limit.
ii.	An extra 15% shall be added to the rates approved vide Sl. No. I to XII below for valuation of Buildings within Coimbatore, Erode and Tiruppur Corporation limits
iii.	An extra 10% shall be added to the rates approved vide Sl. No. I to XII below for valuation of Buildings within Corporation limits of Trichy, Madurai, Salem, Tirunelveli, Thoothukudi and Vellore
iv.	An extra 5% shall be added to the rates approved vide Sl. No. I to XII below for valuation of Buildings within all Municipal limits.
v.	An extra 10% shall be added to the rates approved vide Sl. No. I to XII below for valuation of Buildings located in Nilgiris, Kodaikanal and Yercaud hills, where tourist attractions are more.
b.	The filed Officers are requested to follow the instructions contained in G.O. Ms. No. 329, Finance (Salaries) Department, dated 30.08.2001 in fixation of either new rent or renewal of rent scrupulously, so that there shall not be any extra financial burden to the Government towards the payment of rent to the Private Buildings occupied by the Government Offices.

Sl. No.	Type of construction	Unit	Rates approved for the year 2015-2016 (In Rupees)
I	Class-A		
	Building built with Brick work in lime mortar (or) cement mortar in which teak wood has been used throughout		
1	Roof with RCC Slab		
a	Ground Floor	Sq.m.	6465.00
b	First Floor	Sq.m.	5995.00
c	Second Floor	Sq.m.	6100.00
d	Other upper floors (add extra for each floors)	Sq.m.	92.00
2	Roof with Madras Terrace		
a	Ground Floor	Sq.m.	5915.00
b	First Floor	Sq.m.	5545.00
c	Second Floor	Sq.m.	5635.00
d	Other upper floors (add extra for each floors)	Sq.m.	92.00
3	Roof with Mangalore Tiles over Flat Tiles		
a	Ground Floor	Sq.m.	4705.00
b	First Floor	Sq.m.	4340.00
c	Second Floor	Sq.m.	4425.00
d	Other upper floors (add extra for each floors)	Sq.m.	73.00
4	Roof with Plain Mangalore Tiles		
a	Ground Floor	Sq.m.	4425.00
b	First Floor	Sq.m.	4060.00
c	Second Floor	Sq.m.	4155.00
d	Other upper floors (add extra for each floors)	Sq.m.	73.00
5	Roof with Pan Tiles over Flat Tiles		
a	Ground Floor	Sq.m.	4340.00
b	First Floor	Sq.m.	3970.00
c	Second Floor	Sq.m.	4060.00
d	Other upper floors (add extra for each floors)	Sq.m.	73.00
6	Roof with Pan Tiles without Flat Tiles		
a	Ground Floor	Sq.m.	3875.00

Sl. No.	Type of construction	Unit	Rates approved for the year 2015-2016 (In Rupees)
b	First Floor	Sq.m.	3500.00
c	Second Floor	Sq.m.	3600.00
d	Other upper floors (add extra for each floors)	Sq.m.	73.00
7	Roof with AC Sheet		
a	Ground Floor	Sq.m.	3650.00
b	First Floor	Sq.m.	3290.00
c	Second Floor	Sq.m.	3385.00
d	Other upper floors (add extra for each floors)	Sq.m.	72.35
8	Roof with GI Sheet		
a	Ground Floor	Sq.m.	3750.00
b	First Floor	Sq.m.	3385.00
c	Second Floor	Sq.m.	3470.00
d	Other upper floors (add extra for each floors)	Sq.m.	72.35
	RATE OF DEPRECIATION		1%

Sl. No.	Type of construction	Unit	Rates approved for the year 2015-2016 (In Rupees)
II	Class-A1		
	Building built with Brick work in lime mortar (or) cement mortar in which country wood has been used throughout		
1	Roof with RCC Slab		
a	Ground Floor	Sq.m.	5815.00
b	First Floor	Sq.m.	5260.00
c	Second Floor	Sq.m.	5365.00
d	Other upper floors (add extra for each floors)	Sq.m.	92.00
2	Roof with Madras Terrace		
a	Ground Floor	Sq.m.	5260.00
b	First Floor	Sq.m.	4805.00
c	Second Floor	Sq.m.	4890.00
d	Other upper floors (add extra for each floors)	Sq.m.	92.00
3	Roof with Mangalore Tiles over Flat Tiles		
a	Ground Floor	Sq.m.	4155.00
b	First Floor	Sq.m.	3600.00
c	Second Floor	Sq.m.	3685.00
d	Other upper floors (add extra for each floors)	Sq.m.	73.00
4	Roof with Plain Mangalore Tiles		
a	Ground Floor	Sq.m.	3785.00
b	First Floor	Sq.m.	3320.00
c	Second Floor	Sq.m.	3420.00
d	Other upper floors (add extra for each floors)	Sq.m.	73.00
5	Roof with Pan Tiles over Flat Tiles		
a	Ground Floor	Sq.m.	3685.00
b	First Floor	Sq.m.	3320.00
c	Second Floor	Sq.m.	3420.00
d	Other upper floors (add extra for each floors)	Sq.m.	73.00

Sl. No.	Type of construction	Unit	Rates approved for the year 2015-2016 (In Rupees)
6	Roof with Pan Tiles without Flat Tiles		
a	Ground Floor	Sq.m.	3320.00
b	First Floor	Sq.m.	2950.00
c	Second Floor	Sq.m.	3040.00
d	Other upper floors (add extra for each floors)	Sq.m.	73.00
7	Roof with AC Sheet		
a	Ground Floor	Sq.m.	3385.00
b	First Floor	Sq.m.	3010.00
c	Other upper floors (add extra for each floors)	Sq.m.	72.35
8	Roof with GI Sheet		
a	Ground Floor	Sq.m.	3530.00
b	First Floor	Sq.m.	3155.00
c	Other upper floors (add extra for each floors)	Sq.m.	72.35
	RATE OF DEPRECIATION		1%

Sl. No.	Type of construction	Unit	Rates approved for the year 2015-2016 (In Rupees)
III	Class-B		
	Building built with Brick work in lime mortar (or) cement mortar & partly mud mortar in which teak wood has been used throughout		
1	Roof with RCC Slab		
a	Ground Floor	Sq.m.	5260.00
b	First Floor	Sq.m.	4805.00
c	Second Floor	Sq.m.	4890.00
d	Other upper floors (add extra for each floors)	Sq.m.	92.00
2	Roof with Madras Terrace		
a	Ground Floor	Sq.m.	4705.00
b	First Floor	Sq.m.	4340.00
c	Second Floor	Sq.m.	4425.00
d	Other upper floors (add extra for each floors)	Sq.m.	92.00
3	Roof with Mangalore Tiles over Flat Tiles		
a	Ground Floor	Sq.m.	3685.00
b	First Floor	Sq.m.	3225.00
c	Second Floor	Sq.m.	3320.00
d	Other upper floors (add extra for each floors)	Sq.m.	73.00
4	Roof with Plain Mangalore Tiles		
a	Ground Floor	Sq.m.	3420.00
b	First Floor	Sq.m.	2950.00
c	Second Floor	Sq.m.	3040.00
d	Other upper floors (add extra for each floors)	Sq.m.	73.00
5	Roof with Pan Tiles over Flat Tiles		
a	Ground Floor	Sq.m.	3230.00
b	First Floor	Sq.m.	2860.00
c	Second Floor	Sq.m.	2950.00
d	Other upper floors (add extra for each floors)	Sq.m.	73.00

Sl. No.	Type of construction	Unit	Rates approved for the year 2015-2016 (In Rupees)
6	Roof with Pan Tiles without Flat Tiles		
a	Ground Floor	Sq.m.	2950.00
b	First Floor	Sq.m.	2580.00
c	Second Floor	Sq.m.	2675.00
d	Other upper floors (add extra for each floors)	Sq.m.	73.00
7	Roof with AC Sheet		
a	Ground Floor	Sq.m.	3010.00
b	First Floor	Sq.m.	2645.00
c	Other upper floors (add extra for each floors)	Sq.m.	72.35
8	Roof with GI Sheet		
a	Ground Floor	Sq.m.	3110.00
b	First Floor	Sq.m.	2740.00
c	Other upper floors (add extra for each floors)	Sq.m.	72.35
	RATE OF DEPRECIATION		1.50%

Sl. No.	Type of construction	Unit	Rates approved for the year 2015-2016 (In Rupees)
IV	Class-B1		
	Building built with Brick work in lime mortar (or) cement mortar and partly in mud mortar in which country wood has been used throughout		
1	Roof with RCC Slab		
a	Ground Floor	Sq.m.	4805.00
b	First Floor	Sq.m.	4340.00
c	Second Floor	Sq.m.	4425.00
d	Other upper floors (add extra for each floors)	Sq.m.	92.00
2	Roof with Madras Terrace		
a	Ground Floor	Sq.m.	4245.00
b	First Floor	Sq.m.	3875.00
c	Second Floor	Sq.m.	3970.00
d	Other upper floors (add extra for each floors)	Sq.m.	92.00
3	Roof with Mangalore Tiles over Flat Tiles		
a	Ground Floor	Sq.m.	3320.00
b	First Floor	Sq.m.	2950.00
c	Second Floor	Sq.m.	3040.00
d	Other upper floors (add extra for each floors)	Sq.m.	73.00
4	Roof with Plain Mangalore Tiles		
a	Ground Floor	Sq.m.	3040.00
b	First Floor	Sq.m.	2675.00
c	Second Floor	Sq.m.	2770.00
d	Other upper floors (add extra for each floors)	Sq.m.	73.00
5	Roof with Pan Tiles over Flat Tiles		
a	Ground Floor	Sq.m.	2860.00
b	First Floor	Sq.m.	2490.00
c	Second Floor	Sq.m.	2580.00
d	Other upper floors (add extra for each floors)	Sq.m.	73.00

Sl. No.	Type of construction	Unit	Rates approved for the year 2015-2016 (In Rupees)
6	Roof with Pan Tiles without Flat Tiles		
a	Ground Floor	Sq.m.	2770.00
b	First Floor	Sq.m.	2400.00
c	Second Floor	Sq.m.	2490.00
d	Other upper floors (add extra for each floors)	Sq.m.	73.00
7	Roof with AC Sheet		
a	Ground Floor	Sq.m.	2830.00
b	First Floor	Sq.m.	2470.00
c	Other upper floors (add extra for each floors)	Sq.m.	72.35
8	Roof with GI Sheet		
a	Ground Floor	Sq.m.	2625.00
b	First Floor	Sq.m.	2555.00
c	Other upper floors (add extra for each floors)	Sq.m.	72.35
	RATE OF DEPRECIATION		2%

Sl. No.	Type of construction	Unit	Rates approved for the year 2015-2016 (In Rupees)
V	Class-C		
	Building built with brick work in mud mortar in which country wood has been used throughout		
1	Roof with RCC Slab		
a	Ground Floor	Sq.m.	4075.00
b	First Floor	Sq.m.	3600.00
2	Roof with Madras Terrace		
a	Ground Floor	Sq.m.	3685.00
b	First Floor	Sq.m.	3320.00
3	Roof with Mangalore Tiles over Flat Tiles		
a	Ground Floor	Sq.m.	2860.00
b	First Floor	Sq.m.	2580.00
4	Roof with Plain Mangalore Tiles		
a	Ground Floor	Sq.m.	2580.00
b	First Floor	Sq.m.	2300.00
5	Roof with Pan Tiles over Flat Tiles		
a	Ground Floor	Sq.m.	2490.00
b	First Floor	Sq.m.	2220.00
6	Roof with Pan Tiles without Flat Tiles		
a	Ground Floor	Sq.m.	2300.00
b	First Floor	Sq.m.	2115.00
7	Roof with AC Sheet		
a	Ground Floor	Sq.m.	2555.00
b	First Floor	Sq.m.	2280.00
8	Roof with GI Sheet		
a	Ground Floor	Sq.m.	2645.00
b	First Floor	Sq.m.	2375.00
	RATE OF DEPRECIATION		2%

Sl. No.	Type of construction	Unit	Rates approved for the year 2015-2016 (In Rupees)
VI	Class-D		
	Building built with brick work in lime or cement mortar in which partly wood and partly steel has been used throughout		
1	Roof with RCC Slab		
a	Ground Floor	Sq.m.	4255.00
b	First Floor	Sq.m.	3685.00
c	Second Floor	Sq.m.	3785.00
d	Other upper floors (add extra for each floors)	Sq.m.	92.00
2	Roof with Madras Terrace		
a	Ground Floor	Sq.m.	3785.00
b	First Floor	Sq.m.	3420.00
c	Second Floor	Sq.m.	3505.00
d	Other upper floors (add extra for each floors)	Sq.m.	92.00
3	Roof with Mangalore Tiles over Flat Tiles		
a	Ground Floor	Sq.m.	2950.00
b	First Floor	Sq.m.	2675.00
c	Second Floor	Sq.m.	2770.00
d	Other upper floors (add extra for each floors)	Sq.m.	73.00
4	Roof with Plain Mangalore Tiles		
a	Ground Floor	Sq.m.	2675.00
b	First Floor	Sq.m.	2400.00
c	Second Floor	Sq.m.	2490.00
d	Other upper floors (add extra for each floors)	Sq.m.	73.00
5	Roof with Pan Tiles over Flat Tiles		
a	Ground Floor	Sq.m.	2580.00
b	First Floor	Sq.m.	2300.00
c	Second Floor	Sq.m.	2400.00
d	Other upper floors (add extra for each floors)	Sq.m.	73.00

Sl. No.	Type of construction	Unit	Rates approved for the year 2015-2016 (In Rupees)
6	Roof with Pan Tiles without Flat Tiles		
a	Ground Floor	Sq.m.	2400.00
b	First Floor	Sq.m.	2220.00
c	Second Floor	Sq.m.	2285.00
d	Other upper floors (add extra for each floors)	Sq.m.	73.00
7	Roof with AC Sheet		
a	Ground Floor	Sq.m.	2645.00
b	First Floor	Sq.m.	2280.00
c	Other upper floors (add extra for each floors)	Sq.m.	72.35
8	Roof with GI Sheet		
a	Ground Floor	Sq.m.	2745.00
b	First Floor	Sq.m.	2470.00
c	Other upper floors (add extra for each floors)	Sq.m.	72.35
	RATE OF DEPRECIATION		1.50%

Sl. No.	Type of construction	Unit	Rates approved for the year 2015-2016 (In Rupees)
VII	Class-D1		
	Building built with brick in lime or cement mortar in which steel frame is used throughout		
1	Roof with RCC Slab		
a	Ground Floor	Sq.m.	4350.00
b	First Floor	Sq.m.	3865.00
c	Second Floor	Sq.m.	3970.00
d	Other upper floors (add extra for each floors)	Sq.m.	93.45
2	Roof with Madras Terrace		
a	Ground Floor	Sq.m.	3970.00
b	First Floor	Sq.m.	3590.00
c	Second Floor	Sq.m.	3680.00
d	Other upper floors (add extra for each floors)	Sq.m.	93.45
3	Roof with Mangalore Tiles over Flat Tiles		
a	Ground Floor	Sq.m.	3115.00
b	First Floor	Sq.m.	2835.00
c	Second Floor	Sq.m.	2925.00
d	Other upper floors (add extra for each floors)	Sq.m.	75.95
4	Roof with Plain Mangalore Tiles		
a	Ground Floor	Sq.m.	2835.00
b	First Floor	Sq.m.	2555.00
c	Second Floor	Sq.m.	2635.00
d	Other upper floors (add extra for each floors)	Sq.m.	75.95
5	Roof with Pan Tiles over Flat Tiles		
a	Ground Floor	Sq.m.	2735.00
b	First Floor	Sq.m.	2455.00
c	Second Floor	Sq.m.	2555.00
d	Other upper floors (add extra for each floors)	Sq.m.	75.95

Sl. No.	Type of construction	Unit	Rates approved for the year 2015-2016 (In Rupees)
6	Roof with Pan Tiles without Flat Tiles		
a	Ground Floor	Sq.m.	2555.00
b	First Floor	Sq.m.	2350.00
c	Second Floor	Sq.m.	2435.00
d	Other upper floors (add extra for each floors)	Sq.m.	75.95
7	Roof with AC Sheet		
a	Ground Floor	Sq.m.	2805.00
b	First Floor	Sq.m.	2430.00
c	Other upper floors (add extra for each floors)	Sq.m.	75.20
8	Roof with GI Sheet		
a	Ground Floor	Sq.m.	2900.00
b	First Floor	Sq.m.	2610.00
c	Other upper floors (add extra for each floors)	Sq.m.	75.20
	RATE OF DEPRECIATION		1%

Sl. No.	Type of construction	Unit	Rates approved for the year 2015-2016 (In Rupees)
VIII	Class-E - RCC FRAMED STRUCTURE		
1	Framed structure building built in CM in which TW is used for construction (excluding water supply, sanitary and electrical installations)		
a	Ground Floor	Sq.m.	7180.00
b	First Floor	Sq.m.	6710.00
c	Second Floor	Sq.m.	6805.00
d	Third Floor	Sq.m.	6895.00
e	Other upper floors (add extra for each floors)	Sq.m.	93.45
2	Balcony / Portico projecting outside the face of the building with hand rail with brick work/wood/grill	Sq.m.	2455.00
	RATE OF DEPRECIATION		1%
IX	GODOWN		
2 a	For godowns / Hall type construction with RCC columns and connecting beams etc. with steel trusses and purlins		
	Roofing with A/C sheet	Sq.m.	5330.00
	Roofing with G.I. sheet	Sq.m.	5520.00
b	For godowns / Hall type construction with load bearing type construction with steel trusses and purlins		
	Roofing with A/C sheet	Sq.m.	4945.00
	Roofing with G.I. sheet	Sq.m.	5030.00
	RATE OF DEPRECIATION		1%

Sl. No.	Type of construction	Unit	Rates approved for the year 2015-2016 (In Rupees)
X	Building built with brick work in mud mortar and partly with RR masonry in mud mortar and brick jelly concrete in lime for foundation and ordinary flooring; roofing with RCC/Madras Terrace in which country wood has been used throughout		
1	Roof with RCC slab		
	Ground Floor	Sq.m.	4525.00
	First Floor	Sq.m.	3875.00
2	Roof with Madras Terrace		
a	Ground Floor	Sq.m.	3970.00
b	First Floor	Sq.m.	3420.00
3	Roof with Mangalore Tiles over Flat Tiles		
a	Ground Floor	Sq.m.	3040.00
b	First Floor	Sq.m.	2580.00
4	Roof with Plain Mangalore Tiles		
a	Ground Floor	Sq.m.	2770.00
b	First Floor	Sq.m.	2400.00
5	Roof with Pan Tiles over Flat Tiles		
a	Ground Floor	Sq.m.	2580.00
b	First Floor	Sq.m.	2220.00
6	Roof with Pan Tiles without Flat Tiles		
a	Ground Floor	Sq.m.	2490.00
b	First Floor	Sq.m.	2115.00
7	Roof with AC Sheet		
a	Ground Floor	Sq.m.	2645.00
b	First Floor	Sq.m.	2195.00
8	Roof with GI Sheet		
a	Ground Floor	Sq.m.	2745.00
b	First Floor	Sq.m.	2280.00
	RATE OF DEPRECIATION		2.50%

Sl. No.	Type of construction	Unit	Rates approved for the year 2015-2016 (In Rupees)
XI	THATCHED / TILED ROOF		
1	Building built with brick work in clay and plastered with lime mortar or cement mortar, ordinary grano flooring, white or colour washed, thatched roof either with coconut leaves or palmyrah leaves over CW or bamboo rafters, etc.		
a	Ground Floor	Sq.m.	2100.00
2	Building built with plain mud walls plastered with mud mortar and thatched roof either with coconut leaves of palmyrah leaves over bamboo or country wood rafters etc.		
a	Ground Floor	Sq.m.	1050.00
3	Building built with plain mud walls and plastered with mud mortar & roof with mangalore tiles using bamboo or country wood rafters etc.	Sq.m.	1385.00
4	Building built with plain mud walls and plastered with mud mortar and roof with pan tiles using bamboo or country wood rafters	Sq.m.	1225.00
5	Building built with plain mud walls and plastered with mud mortar and roof with A/C sheet	Sq.m.	1485.00
6	Building built with plain mud walls and plastered with mud mortar and roof with G.I. sheet	Sq.m.	1525.00
	RATE OF DEPRECIATION		4%
XII	GARAGE BUILDINGS		
a	Garage buildings built with brick work in lime or cement mortar and roof with RCC slab in which teak wood or rolling shutters used.	Sq.m.	2770.00
b	Garage building built with brick work in lime or cement mortar with mangalore tile or pan tile roof over flat tiles in which teak wood or rolling shutters used.	Sq.m.	2580.00
	RATE OF DEPRECIATION		1%
c	Garage buildings built with brick work in partly clay and partly lime or cement mortar and roof with RCC slab in which country wood used throughout.	Sq.m.	2675.00
d	Garage building built with brick work in partly clay and partly lime or cement mortar with mangalore tiles or pan tiles roof over flat tiles in which country wood used throughout.	Sq.m.	2300.00
	RATE OF DEPRECIATION		2%

Sl. No.	Type of construction	Unit	Rates approved for the year 2015-2016 (In Rupees)
XIII	MISCELLANEOUS ITEMS		
1	Open area paved either with cement concrete (or) brick (or) stone slabs with retaining walls	Sq.m.	523.00
2	Fencing the area with RCC post and covered either with barbed wire or chain link 1.65m height from Ground level.	RM	387.00
	RATE OF DEPRECIATION		4%
3	Compound wall built in cement or lime mortar to a height of 1.20 metre to 1.50 metre		
	i. Ordinary type 4 1/2" wall thick	RM	925.00
	ii. Ornamental type 9" wall thick	RM	1385.00
4	i. Mosaic flooring grey colour tiles	Sq.m.	513.00
	ii. Mosaic flooring with colour tiles (other than grey)	Sq.m.	578.00
	iii. Dadoing with mosaic in situ	Sq.m.	501.00
5	Cuddapah slab/Shahabad slab flooring	Sq.m.	363.00
6	Flooring with granite slabs 18 to 20mm thick	Sq.m.	1990.00
7	i. Flooring with vitrified tiles	Sq.m.	1310.00
	ii. Dadoing with vitrified tiles	Sq.m.	1130.00
8	i. Flooring with ceramic tiles	Sq.m.	578.00
	ii. Dadoing with Ceramic / glazed tiles	Sq.m.	501.00
9	i. Flooring with marble tiles	Sq.m.	993.00
	ii. Flooring with marble slabs		
	a. for slab of size 1.20 metre and above	Sq.m.	1440.00
	b. for slab of size below 1.20 metre	Sq.m.	1170.00
	RATE OF DEPRECIATION		2%

Sl. No.	Type of construction	Unit	Rates approved for the year 2015-2016 (In Rupees)
10	Iron gates (1.2m height & 3m width)		
	i. Iron gates with ornamental grill	Sq.m.	1270.00
	ii. Iron gates with GI pipe alround & weld mesh inbetween	Sq.m.	795.00
11	Rolling shutters	Sq.m.	1755.00
12	Over head tanks		
	i. In brick work / litre	litre	2.45
	ii. PVC tanks / litre	litre	3.60
13	Municipal Water Tap Service connection	Each	2190.00
14	Hand pump	Each	2190.00
15	Bore well		
	i. upto 50 metre depth / m	RM	134.00
	ii. 50 to 100 metre depth	RM	141.00
	iii. 100 to 200 metre depth	RM	146.00
16	i. Open Well 1.20 metre dia with brick steining 7.50 metre deep	Each	13100.00
	ii. Open well 1.50 metre dia with brick steining 7.50 metre deep	Each	16400.00
	iii. Open well 1.80 metre dia with brick steining 7.50 metre deep	Each	19650.00
	iv. Open well 2.00 metre dia with brick steining 7.50 metre deep	Each	23750.00
17	i. False ceiling using aluminium tees, angles with particle board 60 x 60cm size	Sq.m.	665.00
	ii. Using plywood 5mm thick	Sq.m.	468.00
18	Septic tank built in brick work in cement mortar precast cover slab with inlet and outlet (On volume basis)		
	for 1 cum capacity	Cu.m.	7615.00
19	Inspection chambers with RCC cover slab built in brick work in cement mortar, 23cm thick, plastered and finished		
	i. 60 x 60 x 60cm size	Each	1520.00
	ii. 60 x 60 x 75cm size	Each	1850.00
	iii. 60 x 60 x 90cm size	Each	2280.00

Sl. No.	Type of construction	Unit	Rates approved for the year 2015-2016 (In Rupees)
20	i. Providing IWC with water line, tap, flush out system etc.	Each	3740.00
	ii. Providing EWC 580mm with water line, tap, flush out system etc.	Each	4750.00
21	Wash basin including water line, tap, etc.	Each	1695.00
22	Provision of towel rod and mirror or size 550x440mm	Each	764.00
23	Flat back urinal with water line, valves, etc	Each	1020.00
24	Sink with water line, tap, etc	Each	1695.00
25	Open latrine with 1.80 metre height wall built in brick work in cement mortar.	Sq.m.	2335.00
26	i. Bathroom with GI water line, taps, shower line etc. (minimum room size 1.50m x 1.35m)	Each	3345.00
	ii. Bathroom with PVC water line, tap, shower line, etc. (minimum room size 1.50m x 1.35m)	Each	2930.00
	iii. Bath Tub with all accessories (Porcelain)	Each	12570.00
	iv. Bath Tub with all accessories (built with mosaic finish)	Each	3345.00
XIV I. External Services			
1	50mm dia CI pipe line and specials	RM	403.00
2	75mm dia CI pipe line and specials	RM	567.00
3	100mm dia SW pipe line and specials	RM	127.00
4	150mm dia SW pipe line and specials	RM	210.00
5	100mm dia PVC pipe line and specials	RM	239.00
6	75mm dia PVC pipe line and specials	RM	145.00
II. For Internal			
1	Water supply arrangements (maximum)	on value of building	7.50%
2	Internal sanitary arrangements (maximum)	on value of building	7.50%
3	Internal electrical arrangements (maximum)	on value of building	7.50%

Sl. No.	Type of construction	Unit	Rates approved for the year 2015-2016 (In Rupees)
XV	ELECTRICAL ITEMS		
1	Plug point	Each	205.00
2	Fan point	Each	244.00
3	Light point	Each	233.00
4	1.20m flourescent fitting patty type with tube		
	i. Single	Each	328.00
	ii. Double	Each	595.00
5	40 W flourescent tube (single)	Each	65.60
6	1.20m flourescent fitting box type with tube		
	i. Single	Each	466.00
	ii. Double	Each	730.00
7	i. 1.20m sweep AC ceiling fan with regulator	Each	1600.00
	ii. 1.40m sweep AC ceiling fan with regulator	Each	1725.00
8	EXHAUST FAN	Each	1405.00
9	0.50 HP electric motor pump set		
	i. centrifugal	Each set	6650.00
	ii. Jet type	Each set	8510.00
10	1.00 HP electric motor pump set		
	i. Centrifugal	Each set	8140.00
	ii. Jet	Each set	9990.00
11	1.50 HP electric motor pump set		
	i. Centrifugal	Each set	9620.00
	ii. Jet	Each set	12580.00
12	2.00 HP electric motor pump set		
	i. Centrifugal	Each set	11840.00
	ii. Jet	Each set	15170.00
13	3.00 HP electric motor pump set		
	i. Centrifugal	Each set	14800.00
	ii. Jet	Each set	19900.00
14	5.00 H.P. electric motor pump set (JET)	Each set	24400.00
15	Air-conditioning (on floor area basis)		
	a. Non-Ductable	Sq.m.	3330.00
	b. Ductable	Sq.m.	4450.00
16	i. Lift (G.F. + 4 floors - 8 Passenger capacity)	Each	1225000.00
	ii. Lift (G.F. + 4 floors - 13 Passenger capacity)	Each	1390000.00

for Engineer-in-Chief (Buildings) &
 Chief Engineer (Buildings), PWD,
 Chennai Region, Chennai-5.

PUBLIC WORKS DEPARTMENT

From

Er. T. Kanthimathinathan, M.E., FIE., FIV.,
Engineer-in-Chief (Buildings) &
Chief Engineer (Buildings), PWD, (i/c)
Chennai Region, Chennai-5.

To

- 1. The Chief Engineer (Buildings),**
Public Works Department,
Trichy Region,
Trichy.
- 2. The Chief Engineer (Buildings),**
Public Works Department,
Madurai Region,
Madurai.

Letter No. HDO (B) / 65325 / 2001, dated 17.08.2016

Sir,

Sub: Buildings – Common Schedule of Plinth Area Rates for the purpose of Valuation of Buildings for Rental Calculation by PWD and Collection of Stamp Duty by Registration Department for the year 2015-2016 – **Continuance of Schedule of Plinth Area Rates, 2015-2016 upto 15.08.2016** – Orders issue of – Regarding.


Ref: 1. This office proceedings No. HDO (B) / 65325 / 2001, dt.24.08.15.
2. Engineer-in-Chief, WRD & Chief Engineer (General), PWD, Chennai, letter No. HDO / Sr. DO / 23500 / 2016-1, dt.16.08.16.



I invite your attention to this office proceedings cited, wherein, the Schedule of Plinth Area Rates for the purpose of valuation of building for rental calculation by PWD and collection of stamp duty by Registration Department for the year 2015-2016 was approved and communicated for adoption with effect from 01.08.2015.

The Engineer-in-Chief, WRD & Chief Engineer (General), PWD, Chennai-5 was communicated the Schedule of Rates for the year 2016-2017 with effect from 15.08.2016 vide reference 2nd cited. Therefore, it is informed that the Schedule of Plinth Area Rates, 2015-2016 may be continued for adoption **upto 15.08.2016** for the purpose of valuation of buildings for rental calculations by PWD and collection of stamp duty by Registration Department.

The recast Schedule of Plinth Area Rates for 2016-2017 will be finalised and sent at an early date.


**for Engineer-in-Chief (Buildings) &
Chief Engineer (Buildings), PWD,
Chennai Region, Chennai-5.**

Copy to:

1. The Superintending Engineers of Building Organisation, Public Works Department.
2. The Executive Engineers of Building Organisation, Public Works Department.
3. The Senior Audit Officer, Indian Audit and Accounts Department, Accountant General (Audit) II, Chennai-18.
4. The Inspector General of Registration, No.100, Santhome High Road, Chennai-28.
5. Copy to the Joint Chief Engineer (Buildings), PWD, Chennai-5.
6. Copy to the Deputy Chief Engineer (Buildings), PWD, Chennai-5.
7. Copy to HDO & AEEs of all Technical Sections of EIC (B) & CE (B), CR, PWD, Chennai.
8. Copy to Stock File / Copy to File / Spare copies (50 Nos.).